PACKAGED ROOF TOP UNITS

Supply, deliver, install a Hybrid (VRF condenser) Heat pump Roof Top Package unit as one factory tested functional unit able to run at minus 4 deg C Dry bulb and shall be able to defrost only parts of the condenser coil while still maintaining winter heating to specified capacity (i.e. condenser capacity shall be increased to allow for defrosting).

Full Fresh air unit per specification and drawings single stage filtartion (G4) TC 74.9kW SC 57.9kW (On coil 320C/200C Off coil 13.90C/12.80C) , HC 79.2kW(On coil -40C/-40C Off coil 200C/80C) Supply Air 3300l/s ; 300Pa ESP

Full Fresh air unit per specification and drawings two stage filtration (G4 and F7) TC 61kW SC 50kW (On coil 320C/200C Off coil 14.00C/13.30C) , HC 62.6kW(On coil -40C/-40C Off coil 19.20C/7.70C) Supply Air 2600l/s ;400Pa ESP