Daikin Applied Systems

OFFICIAL TENDER QUOTATION
Ref: DA-MN-26-U2-REV0
Date: 17 March 2026
Validity: 30 Days

Daikin Applied Systems
13600 Industrial Park Blvd, Minneapolis, MN 55441
Tel: +1 (763) 555-0120 | quotes@daikinapplied-us.com

Client: Apex Consulting Engineers | **Project:** Horizon Medical Center - Central Plant Modernization
Equipment Tag: AHU-02 - Cleanroom Air Handling Unit Package

1. Technical Performance Schedule

Parameter	Spec Requirement	Offered by Daikin	Technical Note
Supply Airflow	5300 l/s	**5200 l/s**	Minor deficit (-1.9% within tolerance)
External Static Pressure	1000 Pa	**1000 Pa**	Design match
Fan Arrangement	2x EC500 Plug fans	**2x ebm-papst EC500 Plug fans**	ebm-papst FanGrid array
Fan Power Input	8382 W (8.4 kW)	**8382 W**	400V / 3Ph / 50Hz
Cooling Coil Capacity	56.4 kW	**55.0 kW**	Minor duty deficit (-2.5%)
Entering Air Conditions	22.0 °C DB / 15.7 °C WB	**22.0 °C DB / 15.7 °C WB**	Design match
Leaving Air Conditions	14.5 °C DB / 12.3 °C WB	**14.5 °C DB / 12.3 °C WB**	Design match
DX Coil Materials	SS casing, Cu tubes, Al fins	**Galvanized casing, Cu/Al fins**	Galvanized casing (Spec SS)
Condensate Drip Tray	1.2mm SS V-shape sloped	**1.2mm 304 SS V-shape sloped**	Center drain Ø28mm
Base Frame	100 x 50 galv channel	**100 x 50mm Galv channel**	Bolted tapered flange
Panels & Insulation	50mm Chromadek double-skin	**50mm Chromadek double-skin**	Polystyrene insulated
Primary Filtration	G4 / EU4 (50mm washable)	**G4 Primary washable panel (50mm)**	6x 592x592 & 3x 592x292
Secondary Filtration	F8 Bag Filter (300mm soft)	**F8 Soft Bag Filter (300mm)**	6x 592x592 & 3x 592x292
Differential Gauge	Magnehelic gauge fitted	**Dwyer Magnehelic gauge fitted**	Across filter banks
Electrical & Controls	Isolator, E-Stop, lights, panel	**Isolator, E-Stop, lights, panel**	Pre-wired factory panel
VRF Interface Kit	VRF kit fitment	**Excluded (By VRF contractor)**	Non-compliant (VRF kit omitted)
Sloped Weather Roof	90mm to 50mm slope	**90mm to 50mm sloped roof**	Weather cowl fitted
Unit Weight	1155 kg approx	**1165 kg approx**	Verified engineering weight

2. Commercial Pricing & Scope Demarcation

Scope Item	Terms / Clarification	Amount (USD)
Daikin D-AHU Unit 2	Manufactured and factory tested	**$ 21,900.00**
Delivery to Jobsite	Delivered roadside	**Included**
VRF Expansion Kit	Omitted (by VRF vendor)	**Excluded**

Authorized Representative: Marcus Engel, Technical Specialist | *Technical Sales Division* (E&OE;)